

TO INSTALL:

IMPORTANT - DO NOT disconnect lead wires from the Master Control Panel when making installation. 1. Tilt and pass Control Panel and electrical box through the countertop cutout, then through the apron cutout. Lower modular section into countertop cutout and

position. RECOMMENDATION: Before final seating of modular section to countertop, apply a bead of silicone adhesive/sealant to the underside of gasket supplied on the mounting fla<u>n</u>ge.

From underneath, insert screwdriver into slots in
From underneath, insert screwdriver into slots in
Wellslock frame and twist ears outward (clockwise) as required to secure flange tightly to countertop.
Mount Control Box to apron cutout as shown in drawing.
Mount Control Panel onto electrical box using the screws supplied.

TO PLUMB:

A drain with valve is supplied on all units. Location of the valve handle is at the discretion of the fabricator (see drawing).
Connect 1" drain connection to a suitable drain line.

TO WIRE:

1. Final connection is accomplished by bringing proper power supply leads (see "WIRING REQUIREMENTS" label) through conduit knockout to wire leads supplied within the Master Control Panel. Check nameplates for voltage and phase.

NOTES:

BAIN MARIE STYLE HEATED TANKS ARE DESIGNED FOR WET OPERATION ONLY.

THIS EQUIPMENT IS TO BE INSTALLED TO COMPLY WITH APPLICABLE FEDERAL, STATE OR LOCAL PLUMBING AND ELECTRICAL CODES.